

# FRAMELESS END DUMP



- ✓ **Tube Length**  
32' 26c/y +/- 3%    34' 27c/y +/- 3%    36' 28c/y +/- 3%
- ✓ **Dimensions**  
Tub length, 102" width, 45" side height
- ✓ **Weight**  
32' 14,950 lbs    34' 15,250 lbs    36' 15,500 lbs
- ✓ **Tub steel**  
Available in 1/4" AR400, AR450, AR500 steel. The last 8ft are in 5/16" steel.
- ✓ **Nose & gate**  
1/4" AR400 plate (also available in AR450 & AR500 steel)
- ✓ **Tailgate**  
Air-operated Hi-Lift, integrated mud flaps
- ✓ **Optional front fenders**  
Steel bolt-on fenders (also available in aluminum)
- ✓ **Rear fenders**  
Steel bolt-on fenders (also available in aluminum)
- ✓ **Ladder**  
Located in the front
- ✓ **Hoist**  
8"-5 stage custom hoist
- ✓ **Rear gate cylinders**  
4" air operated cylinders
- ✓ **Gate valve**  
Rexroth valve, controlled manually and from cab
- ✓ **Suspension**  
Hutch H-900 2-spring single point suspension
- ✓ **Axles**  
77.5" track axles
- ✓ **Wheels**  
8 - 8.25 x 24.5 steel wheels
- ✓ **Tires**  
8 - 11R x 24.5 tires
- ✓ **Landing Gear**  
Drop down adjustable landing legs
- ✓ **Lights**  
Full DOT approved LED sealed lights with junction box
- ✓ **ABS**  
ABS sensor on rear axle
- ✓ **Paint**  
Sandblasting  
Acid wash  
Phosphate treatment  
Heated silicon treatment  
Powder coat finish
- ✓ **Available options**  
Air-ride suspension  
Lift axles  
Numerous tarp options  
Custom lengths & side heights  
Wheels & tire options  
Various color options



movingforward@durahaul.com  
US toll free 844-877-6221

WWW.DURAHHAUL.COM



## Commercial Trailer Products

4132 Irving Blvd | Dallas, TX 75247 | 214-637-0080  
1605 Ackerman Rd | San Antonio, TX 78219 | 210-661-4592

peaktrailergroup.com



DH-34FTHRED-1216